

FUEL PUMP INSTALLATION CHECKLIST

To protect your warranty, assure the following steps have been accomplished prior to operating your new pump.

1. Force flushing multi-bay wet wing fuel tank systems.
2. Thorough internal inspection of each of the fuel tank bays.
3. Removal of accumulated water and debris.
4. Check all lines for dry rot and damage.
5. **DO NOT RUN DRY** - Prime upon installation and never run pump dry.
6. **DO NOT** use Teflon tape or sealant of any kind.
7. **DO NOT** open or disassemble pump at any time.